



NOTE:

1. Freshwater supply for rinse: G3/4", 150-600 KPa, ≥340L/h, filling temperature 10-82 °C, must be cold if condenser is fitted;
- freshwater supply for fill : G3/4", 150-600 KPa, ≥340L/h, filling temperature 50-60 °C.
2. Tank drain: DIN50, siphon by customer.
3. Electrical connection:

Model	Voltage	Power	Fuse	Cross section
CCA-3853-RS-24-H	380V 50Hz 3N~	38.5kW	60A	25mm2
CCA-3853-RS-34-H	380V 50Hz 3N~	44.5kW	78A	35mm2
CCA-3853-RS-44-H	380V 50Hz 3N~	50.5kW	87A	35mm2
CCA-3863-RS-24-H	380V 60Hz 3N~	38.5kW	60A	25mm2
CCA-3863-RS-34-H	380V 60Hz 3N~	44.5kW	78A	35mm2
CCA-3863-RS-44-H	380V 60Hz 3N~	50.5kW	87A	35mm2
CCA-3853-RS-25-V	380V 50Hz 3N~	44.5kW	78A	25mm2
CCA-3853-RS-35-V	380V 50Hz 3N~	50.5kW	87A	35mm2
CCA-3853-RS-45-V	380V 50Hz 3N~	56.5kW	87A	35mm2
CCA-3863-RS-25-V	380V 60Hz 3N~	44.5kW	78A	25mm2
CCA-3863-RS-35-V	380V 60Hz 3N~	50.5kW	87A	35mm2
CCA-3863-RS-45-V	380V 60Hz 3N~	56.5kW	87A	35mm2
CCA-2253-RS-23-H	220V 50Hz 3~	32.5kW	87.5A	35mm2
CCA-2253-RS-22-H	220V 50Hz 3~	26.5kW	72A	25mm2
CCA-2253-RS-23-V	220V 50Hz 3~	32.5kW	87.5A	35mm2
CCA-2253-RS-22-V	220V 50Hz 3~	26.5kW	72A	25mm2
CCA-2253-RS-20-V	220V 50Hz 3~	14.5kW	40.5A	16mm2
CCA-2253-RS-30-V	220V 50Hz 3~	20.5kW	56A	16mm2
CCA-2263-RS-23-H	220V 60Hz 3~	32.5kW	87.5A	35mm2
CCA-2263-RS-22-H	220V 60Hz 3~	26.5kW	72A	25mm2
CCA-2263-RS-23-V	220V 60Hz 3~	32.5kW	87.5A	35mm2
CCA-2263-RS-22-V	220V 60Hz 3~	26.5kW	72A	25mm2
CCA-2263-RS-20-V	220V 60Hz 3~	14.5kW	40.5A	16mm2
CCA-2263-RS-30-V	220V 60Hz 3~	20.5kW	56A	16mm2
CCA-2053-RS-20-V	200V 50Hz 3~	14.5kW	43A	16mm2
CCA-2053-RS-30-V	200V 50Hz 3~	20.5kW	61A	25mm2

WARNING:
Installation should comply with all National and Local codes at practice.

Model:

- CCA-385(6)3-RS-2(3)4)5(4)-V(H)
- CCA-225(6)3-RS-2(3)3(0)-V(H)
- CCA-2053-RS-2(3)3(0)-V(H)

- 1、 Tank filling connection G $\frac{3}{4}$.(1 will be rinse filling if without booster)
- 1.1、 Rinse filling connection G $\frac{3}{4}$.(1.1 will be tank filling if without booster)
- 2、 Tank drain DIN50
- 3、 Power line inlet
- 4、 Exhaust 600m3/h



4. Exhaust connection: outlet total above 600 m3/h.
5. Must install the main switch to disconnect electrical power to the machine and manual shut off valves for water.
6. All drain and ventilation connections must be made in accordance with National codes.
7. Pipework external of the machine is to be done on site.